



NTB  
INTERSTAATLICHE HOCHSCHULE  
FÜR TECHNIK BUCHS

**WPZ**  
*Wärmepumpen-Testzentrum*

# Heat pump test center WPZ

Mick Eschmann

[mick.eschmann@ntb.ch](mailto:mick.eschmann@ntb.ch)


[www.wpz.ch](http://www.wpz.ch)

+41 81 755 34 02

- Measurement of domestic hot water heat pumps according to EN 16147


# Standard

Design of test bench:



# Standard

Measurement for DHW carries out according to EN 16147:



- 1: heating up period
- 2: standby period
- 3: determination of  $COP_{DHW}$
- 4: determination of reference hot water temperature

# Standard

## 1: heating up period

- Water will heat up from 10 °C until the first time compressor is switched off by the thermostat (around 55 °C)

## 2: standby period ( $P_{sb}$ )

- The standby power input is determined by measuring the electrical power input over an integral number of on-off cycles of the compressor. The test shall be performed over a period of minimum 48 h.

## 3: determination of COP (draw-offs)


Profile	S	M	L	XL	XXL
Individual draw-off per day [kWh]	2.10	5.85	11.66	19.07	24.53

## 4: determination of reference hot water temperature

- This test is started when the compressor switches off at the end of the last measurement period for the load profile. A continuous hot water draw-off is started and continues until the hot water temperature falls below 40 °C.

# Standard

## Determination of COP




## COP values (measured by WPZ)

Source temperature	+7 °C	+20 °C
COP: DHW-HP	1.82 to 3.18	2.68 to 4.20
COP: HP with separated DHW tank	1.78 to 3.17	-


*Results are only considered between 2015 and 2018*

# Standard

COP as a function of load profile:



# Standard



# Many thanks for attention



Wärmepumpen-Testzentrum WPZ

Mick Eschmann

E-Mail: [mick.eschmann@ntb.ch](mailto:mick.eschmann@ntb.ch)

Tel: +41(0)81 755 34 02

[www.wpz.ch](http://www.wpz.ch)